

PVC Rigid Electrical Conduit

Schedule 40 Conduit



Tested and Certified by ETL Intertek to **UL 651**

-  Conduit is manufactured to be in conformance with NEMA TC 2 and UL 651.
-  Designed and produced for use in both above ground and below ground applications.
-  Product manufactured with one integral solvent-weld bell standard per length.

Nominal Size	Dimensions (inches)		Approximate Weight per 100' (pounds)	Standard Crate Quantity (feet)	
	Outside Diameter (Average)	Wall Thickness (Minimum)		10'	20'
½	0.840	0.109	17	6,000	12,000
¾	1.050	0.113	22	4,400	8,800
1	1.315	0.133	33	3,600	7,200
1 ¼	1.660	0.140	44	3,300	6,600
1 ½	1.900	0.145	53	2,250	4,500
2	2.375	0.154	73	1,400	2,800
2 ½	2.875	0.203	116	930	1,860
3	3.500	0.216	161	880	1,760
3 ½	4.000	0.226	194	630	1,260
4	4.500	0.237	230	570	1,140
5	5.563	0.258	311	380	760
6	6.625	0.280	404	260	520
*8	8.625	0.322	607	140	280

*8" Sch40 is not included in UL 651 and is therefore not listed.